

# Project X Status Report

Sergei Nagaitsev (Fermilab)

March 11, 2010

<http://www.fnal.gov/pub/projectx/>





- 
- Previous Project X presentation at HEPAP
    - S. Holmes, Nov 13, 2008
  - Developments since Nov 2008
    - Evolution of initial configuration
    - Preliminary IC-1 and IC-2 estimates
    - 4<sup>th</sup> Project X Physics Workshop  
[http://www.fnal.gov/directorate/Longrange/Steering\\_Public/workshop-physics-4th.html](http://www.fnal.gov/directorate/Longrange/Steering_Public/workshop-physics-4th.html)
    - Collaboration
  - Technical and cost optimization
  - Strategy
    - Cost range strategy





- Long-Baseline  
Neutrino Experiment: 2 MW at 60-120 GeV
  - well understood beam requirements;
  - it will be supported in any configuration we select.
- Rare Processes:  $\geq$  several 100's kW at 2.x – 8 GeV
  - well understood beam requirements for this mission.  
4<sup>th</sup> Project X Physics Workshop (Nov 2009)
- NF/MC Platform: upgradable to 4 MW at 5 – 15 GeV
  - MC beam requirements are (x~10) harder than NF;
  - High on our “radar screen” but is not a driver;
  - Do not need to have it on day 1 of initial program;  
need to demonstrate a plausible path.

Concurrent



- IC-1 has been based on ILC-technology with a pulsed, 325-MHz low-energy and 1.3GHz high-energy SC linac (8 GeV)
- Objectives for the initial proposal (September, 2007)
  - ILC technology test (360 kW proton beam power at 8 GeV)
  - 2 MW at (60 -120 GeV) in the Main Injector for neutrinos
  - 100-200 kW at 8 GeV for rare processes (muons and kaons)
  - Replacement for a ~40 year-old Booster & Linac
- Final IC-1 (as of spring 2009)
  - 2 MW at (60 -120 GeV) in the MI for neutrinos (LBNE)
  - ~300 kW at 8 GeV for rare processes
    - 150 kW to Mu2e (Phase 2) upgraded (with a slow extraction)
  - Reduced coupling to ILC (500 kW proton beam power at 8 GeV)
  - Improved but still comparatively narrow physics program

## IC-1





- Rare processes require a stream of bunches with a  $\sim 100\%$  duty cycle.

Examples:

	Train Frequency	Pulse Width (nanoseconds)
Kaon experiments	20-30 MHz	<0.2
Muon conversion experiment	0.5-1.0 MHz	<100
$\mu \rightarrow e\gamma$ & $\mu \rightarrow eee$ experiments	80-300 MHz	<0.2


- A pulsed beam from linac is not optimal; requires beam conditioning in rings and slow extraction.
- There is a fundamental limit to slow extraction: losses at the electrostatic septum
  - Also, space-charge for short bunches, single user for a given bunch format, non-uniform spill rates
  - World's best: AGS, 70 kW (2% loss), unbunched beam (25 GeV); similar beam power from Tevatron in the past
  - JPARC design: several 100 kW at 50 GeV, unbunched (undemonstrated)
- At the end, we understood that slow extraction is the bottleneck.



- Mar. 2009: To improve the rare processes program we have focused on a cw proton linac.

## Missions:


- 2 MW at 60-120 GeV in MI for LBNE
  - Same as in IC-1
- Diverse program with muon, kaon, and nuclear physics
  - Different experiments require different time structures
  - “unlimited” beam power on target
- 8 GeV program with a single turn extraction ( $\geq 100$  kW)
  - g-2, ...
- A path to MC/NF
- Experiments in other fields
- **CEBAF is an example of such a machine with e-beam**





- 
- IC-2 concept (as of end of summer 2009)
    - 2.0 GeV CW linac
    - potentially “unlimited power”
    - RF separation + bunch-by-bunch chopping
    - Multiple experiments operating simultaneously
    - Independent bunch structure control
  
  - “Pulsed” 2-to-8 GeV acceleration (10 Hz, 4.3 ms, 5% duty cycle) to support MI program
    - Both synchrotron and pulsed SC linac are a good choice

# IC-2 Overview





## 1 $\mu$ sec period at 2 GeV

mu2e pulse ( $9e7$ ) 162.5 MHz, 100 nsec



400 kW

Kaon pulse ( $9e7$ ) 27 MHz


800 kW

Other pulse ( $9e7$ ) 27 MHz

800 kW





# IC-2 Provisional Siting



# Initial Configuration-2

## Technology Map

### 2-GeV Super Conductive cw linac





- IC-1 point estimate completed March 2009, subject to Director's Review
  - Assessed to be conservative w/ caveats: escalation, scope, schedule
- IC-2 point estimate completed in October 2009
  - Same estimators and methodology as IC-1
  - Not yet reviewed
  - ~6% higher than IC-1 – within range of error.

	IC-1 (\$M)	IC-2 (\$M)
Base Cost	\$743.5	\$798.4
Overhead	\$185.9	\$187.5
Escalation	\$135.7	\$144.0
Contingency (40%)	\$426.1	\$452.0
<b>Total</b>	<b>\$1,491.2</b>	<b>\$1,581.9</b>

# Project X 4<sup>th</sup> Project X Physics Workshop

November 9-10, 2009



- Identified optimum energies for various programs

	Proton Energy (kinetic)	Beam Power	Beam Timing
Rare Muon decays	2 – 3 GeV	> 500 kW	1 kHz – 160 MHz
Precision $K^0$ studies	2.6 – 3 GeV	> 200 kW	20 – 160 MHz (< 50 psec pings)
Rare Kaon decays	2.6 – 4 GeV	> 500 kW	20 – 160 MHz (< 50 psec pings)
(g-2) measurement	8 GeV	20 – 50 kW	30 - 100 Hz
Neutron and exotic nuclei EDMs	1.5 – 2.5 GeV	> 500 kW	> 100 Hz




- 
- Solved the IC-1 problems (slow extraction)
  - But...
  - two issues remained...
    1. Low proton beam energy (2 GeV instead of 3)
    2. Inefficient acceleration in the linac




- What problem are we trying to solve?

## Energy gain/cavity in IC-2




- 1300 MHz section is not an efficient accelerator (for protons)
- Primary culprit is transit factor
  - also, number of cells per cavity
- Maximal gain at zero synchronous phase is 17 MeV (for  $\beta=1$ ) but for a 2-GeV proton beam it is close to 15 MeV

# Several 3-GeV linac schemes analyzed






- Option 4: a 3-GeV CW linac with a 650 MHz intermediate system, based on 5-cell cavities.



Note: 650 MHz,  $\beta=0.9$ , 5-cell cavities are same physical length as 1300 MHz,  $\beta=1.0$ , 9-cell cavities



### Energy gain/cavity in IC-2v2.0



Discontinuity can be effectively eliminated with a  $\beta=0.95$  cavity



- Total number of cavities in each configuration:  
IC-2v1.0: 316 cavities (to 3 GeV)  
IC-2v2.0: 250 cavities (less if  $\beta=0.95$ )
- Total linac length is reduced by ~20% (for 3 GeV)
  - Or, 3 GeV linac (option 4) is ~20% longer than the 2 GeV linac in IC-2v1.0
- Early analysis of cost trade-offs indicate that 1300 MHz cavity becomes more cost effective than 650 MHz somewhere in the range of 2 GeV
- Development of IC-2v2.0 (option 4) will allow us to explore issues related to introduction of a third frequency, and variations on the 1300 MHz cavity shape

# Short Term Strategy

## (Next 6 months)



- Develop an estimate for a 3 GeV CW linac operating at 1.5-2 MW
  - Identify (cost) break points (with respect to beam power) on the rf system and cryogenics distribution system
  - Establish a better optimized (i.e. reduced cost) linac configuration: cavity types, cavity frequencies, and transition points
- Retain RCS within the estimate but limit work to critical issue(s)
  - Injection
- Investigate options for pairing a 3-8 GeV pulsed linac to CW front end
- Update RD&D Plan to cover CW linac
- Archive ICD-1 and associated cost estimate
- Proposed strategy for CD-0
  - Attempt to get cost of 3 GeV linac at or below \$1.0 B
  - Conduct a Director's Review to validate a cost range that extends below \$1.0 B



- 
- Goals of the Director's Review:
    - Validate the cost estimate for IC-2
    - Validate a cost range proposed by the project
  - Upper end of range = **IC-2v1.0**, with linac at 3.0 GeV/1.0 mA. RCS, Recycler, MI
    - Release ICD-2V1.0 as is (2.0 GeV) after final edit
    - Update the estimate with the incremental cost of adding 1 GeV of CW linac
  - Lower end of range = **IC-2v2.0**, with linac at 3.0 GeV/0.5 mA, no RCS, Recycler, MI
    - Update to ICD-2V2.0 based on “Option 4” configuration
    - Update the cost estimate based on “Option 4” configuration



- A multi-institutional collaboration has been established to execute the Project X RD&D Program.
  - Organized as a “national project with international participation”.
    - Fermilab as lead laboratory
    - International participation via in-kind contributions, established through bi-lateral MOUs. (First MOU with India in place)
  - Collaboration MOU for the RD&D phase outlines basic goals, and the means of organizing and executing the work. Signatories:

ANL	ORNL/SNS
BNL	MSU
Cornell	TJNAF
Fermilab	SLAC
LBNL	ILC/ART
  - Collaborators to assume responsibility for components and sub-system design, development, cost estimating, and potentially construction .



- 
- The configuration for Project X has evolved to maximize physics outcome since the initial proposal in 2007
    - At every step we have improved the performance
    - A new approach to high-duty factor beams and rare processes
    - Not another rendition of JPARC
    - x10 beam power of the IC-1 rare-process program, x7 goal of JPARC
    - Capture leadership in intensity frontier
  - We now know what we want to build!
  - We propose to build Project X based on a 3-GeV CW linac.
    - Could be constructed in a 5-year time period
    - Multi-user facility concurrent with LBNE
    - An rf splitter sends beam to 3 users (muon, kaon and nuclear physics), but technology is not limited to 3 users.

# Backup: Potential cost reductions



- Extend cost range further downward by establishing a set of potential cost reductions that can be applied to either configuration
    - Reoptimization of linac configuration
    - Review of CM estimate to identify cost reduction opportunities
    - Identify rf infrastructure that is frequency independent vs dependent
    - Review of rf power and distribution system to identify breakpoints (with respect to beam current)
    - Review the cryo estimate to identify breakpoints with respect to segmentation, and complete G vs Q vs T
    - Identify potential in-kind contributions from international partners
    - Remove space offset budgets
    - Develop a reduced overhead model
    - Update R&D plan to configuration IC-2
- ⇒ Consolidate all of the above into a cost opportunities spreadsheet

# Backup: Project management




- We have assembled a senior management team (3 people part-time)
  - assembled a team of level-2 managers (all part-time)
- We are preparing an integrated SCRF plan
  - includes our commitments to the ILC program (1.3 GHz, pulsed)
- The FY2010 budget for Project X is \$10.3M. Of this \$1.6M is set aside for work at the collaborating institutions.

# Integrated SRF Plan Cryomodules



U.S. Fiscal Year	2008	FY09	FY10	FY11	FY12	FY13	FY14	FY15
<b>1.3 GHz</b>								
CM1 (Type III+)		CM Ass'y	Install CM	CM Test				
CM2 (Type III+)		Omnibus Delay	Process & VTS/Dress/HTS		CM Ass'y	sw ap		
CM3 (Type IV)			Design	Order Cav & CM Parts		2/3 CM		
CM4 (Type IV)						sw ap		
CM5 (Type IV)						sw ap		
CM6 (Type IV+) CW Design					Design CM 1.3 GHz CW			Install in CMTF
NML Extension Building		Design	Construction					
NML Beam					Move injector/install beam components	Beam Available to RF Unit test except during installation periods (contingent upon cryogenic load/capacity)		
CMTF Building			Design	Construction				
<b>650 MHz</b>								
Single Cell Design & Prototype								
Five Cell Design & Prototype								
CM650_1				Design	Order 650 Cav & CM Parts	Process & VTS/Dress/HTS	650 CM Ass'y	
<b>325 MHz</b>								
SSR0/SSR2 Design & Prototype				Design (RF & Mechanical) all varieties of Spoke Reonators	Prototype (as required)	Process & Test (as required)		
SSR1 Cavities in Fabrication (14)			Procurement (already in progress)	Process & VTS/Dress/HTS				
CM325_1				Design	Procure 325 CM Parts	325 CM Ass'y		





U.S. Fiscal Year	2008	FY09	FY10	FY11	FY12	FY13	FY14	FY15	
Nb Scan/Dress <b>Cavity</b> Facility Upgrade	Omnibus Delay	Upgrade Complete					Upgrade Complete		
325/650 MHz Cavity Facility Upgrade					Upgrade Complete				
<b>CAF</b> Assembly Upgrade		Upgrade Complete							
325/650 MHz CAF Upgrade						Upgrade Complete			
<b>VTS 2 &amp; 3</b> Upgrade			VTS2 Procure FNAL	VTS2 Complete	VTS2 Complete	VTS3 Procure India	VTS3 Complete		
325/650 MHz VTS Upgrade					Upgrade Complete				
<b>HTS 2</b> Construction				Design	Procure India		HTS2 Complete		
<b>NML</b> Beam Line		Design	Procure		Install	NML Complete			
NML Refrigerator			Design	Procurement				Operate NML Ref	
NML Cryo Distribution System								CDS Complete	
SLAC Refrigerator				Design SLAC Ref Interface (as req'd)			SLAC Refrig Oper		
<b>CMTF</b> CM Test Stand (1.3 GHz)							Procure FNAL		1.3 CMTS Complete
650 MHz CM Test Stand							Procure India	650 CMTS Complete	
CMTF Cryo Distribution System							Procure FNAL		CMTF Dist Complete
<b>MDB</b> Spoke Test Cryostat 2k Upgrade						325 HTS Upgraded			
325 MHz CM Test Stand @ MDB						Procure FNAL		325 CMTS Complete	
325 Cryo Distribution Upgrade					Upg TL to 325 HTS		TL to 325 CMTS	325 CDS Complete	
MDB Cryo Upgrade (FY15 & beyond)									Des/add 4th Refrig
<b>ANL &amp; JLAB EP</b> upgrades		ANL EP Oper	JLab Upg Des	Procure	Upgrade Complete				
325/650 MHz Proc. Upgrade				ANL Upg Des		Upgrade Complete			

